BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE-B

Name of Work :"Providing and Fixing of SWD boundary poles and chain link fencing at vulnerable locations of SWD in ward No. 08"

Sl no.	Description	Unit	Qty.	Sanctioned Rate in Rs.	
				Rate in Figures	Rates in Words
1	2	3	4	5	6
1	Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of servicable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thicknesscomplete as per specifications. II. By Mechanical means: A. In Area of light jungle	Ha	0.88	15000.0	Rupees Fifteen Thousand only
2	Providing and fixing RCC precast fencing pole of size0.15mX0.15X2.0m casted in CC 1:1.5:3 with 20mm downsize agregate making holes for drawing darbed wire at 30cm C/C using 10mm dia vertical 4 TMT steel roads and 8mm dia stirrups at 15cm C/C using 1.5m above ground level using steel moulding, curing transportation to work spot including excavation in hard soil fixing in plan cement concrete 1:2:4 using 20mm down size aggregate including aligning to plumb and line providing including cost of all materials, labour, hire charge of machineries lead, lift loading and loading etc.. complete	Each	125.00	1750.0	Rupees Thousand Seven Hundred Fifty only
3	Painting two coats on new concrete surface:painting two coats after filling the surface with synthetic enamel point in all shades on new plasteres concrete surface complete peer specification Morth specification No.803	Sqm	127.50	50.0	Rupees fifty only
4	Painting new letter and figures of any shade with synthetic enamel point block or any other approved colour to give an even shade complete as per specification.(ii) english and Roman hyphaen and the like not to be measured an paid for Morth specification No801	cm	1750.00	5.0	Rupees Five only
5	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications	cum	13.75	125.0	Rupees One hundred and Twenty Five only
6	Providing and laying in position plain cement concrete of mix 1:2:4 with OPC cement @ 240kgs, with 40mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @ 0.459cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	11.25	5000.0	Rupees Five Thousand only

H. Shakar Shakar

Scanned with CamScanner

Sl no.	Description	Unit	Qty.	Sanctioned Rate in	
				Rate in Figures	Rates in
7	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)	Rmt	150.00	850.0	RupeesEight hundred and Fifty only
8	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint	Rmt	400.00	400.0	Rupees Four Hundred only
9	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint	Sqm	240.00	700.0	Rupees Seven Hundred inly
10	Providing J.C.B. Excavator on Hire basis including operator and Fuel	days	11.00	5000.0	Rupees Five Thousand only

M. chandar Shekar

Contractor

12/6/2020

Executive Engineer
SWD, Yelahanka Zone

Scanned with CamScanner